

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

ne of Work :- Filling of pot holes Main & Cross roads in Dasarahalli Ward No

Est. Cost Rs 10.00 Lakhs

Description of item	Unit	No	L	B	D	Qty	Rate	Amount
Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant arriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 106 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2016-17, P.No.155 I do 20 18)								
Bhuvaneshwari Nagara C/R	Cum	4	3.00	3.00	0.20	36.00		
Bhuvaneshwari Nagara 1st Main		2	2.50	2.80	0.20	14.00		
Kempe gowda Nagara C/R		5	2.30	3.00	0.20	34.50		
St.Mary's School Road & C/R		4	2.50	3.00	0.20	30.00		
Dasarahalli Main road		3	3.00	3.00	0.20	27.00		
Ramesh road		5	2.00	2.60	0.20	26.00		
Prashanth nagagra C/R		5	2.20	3.00	0.20	33.00		
Kalasti Nagara temple road		4	2.50	2.50	0.20	25.00		
Kalasti Nagara Cross roads		4	2.00	3.00	0.20	24.00		
Pipe line road		5	2.60	4.50	0.20	58.50		
M Road		4	5.00	5.00	0.20	100.00		
Basic Rate	1888.00					408.00	2001.28	816522.00
Add Area Weightage 6%	113.28							
Total	2001.28							

KSRRB 3000 Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, applying tack coat on the sides and base of excavation at 2.5kg/10sqm as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 including cost of materials, labour, HOM complete as per specifications. MORTH Specification No. 3004.2 It.No 35.5 P- PWD SR 2018-19

Bhuvaneshwari Nagara C/R	Cum	4	3.00	2.00	0.25	6.00		
Bhuvaneshwari Nagara 1st Main		2	2.50	1.20	0.25	1.50		
Kempe gowda Nagara C/R		5	2.30	1.50	0.25	4.31		
St.Mary's School Road & C/R		4	2.50	1.50	0.25	3.75		

Dasarahalli Main road	3	3.00	2.00	0.25	4.50		
Dasarahalli Road	5	2.00	1.50	0.25	3.75		
Dasarahalli nagagra C/R	5	2.20	2.00	0.25	5.50		
Dasarahalli Nagara temple road	4	2.50	2.00	0.25	5.00		
Dasarahalli Nagara Cross roads	4	3.50	1.80	0.25	25.20		
Dasarahalli line road	5	2.60	2.00	0.25	6.50		
Dasarahalli M Road	4	5.00	2.50	0.25	12.50		
					78.51	365.70	28711.00
Basic Rate	345.00						
Add Area Weightage 6%	20.70						
Total	365.70						
Sub Total						845233	
Tender Premium Charge 5%						42262.00	
PMC Charge 1%						8452.00	
GST Charge 12%						101428.00	
Miscellaneous and Unforeseen Charges						2625.00	
Total						1000000.00	
(Rupees Ten Lakhs Only)							

CERTIFICATE

The Work spot has been inspected and the work is found to be necessary
 The Estimate is prepared as per the PW.P & IWTD - SR - 2018-19
 The Provision made in estimate are adequate and essential
 This area comes under B.B.M.P Limits.

Assistant Engineer
 Ward-15

Assistant Executive Engineer
 T. Dasarahalli Sub-Division
 B.B.M.P

Executive Engineer
 Dasarahalli Division
 B.B.M.P. Bangalore.

ನಂ. EE/DD/AS/122/19-20 ದಿನಾಂಕ : 17/06/19

ರೂ. 10.00 Lakhs/- (Ten Lakhs only)

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಧಾರಿತವಾಗಿ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂಕರರು
 ವಿ.ವಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
 ದಾಸರಹಳ್ಳಿ, ಬೆಂಗಳೂರು

ನಂ. EE/DD/TS/56/2018-19 ದಿನಾಂಕ : 30/01/2019

ರೂ. 10.00 Lakhs/- (Ten Lakhs only)

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂಕರರು
 ವಿ.ವಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
 ದಾಸರಹಳ್ಳಿ, ಬೆಂಗಳೂರು